ADDENDUM 5
Section 01 22 00 Unit Prices

The following unit prices are requested, but since there is no place on the proposal form for unit prices, please provide prices below.

3.2 SCHEDULE OF UNIT PRICES

A. Unit Price No. 1 - Earthwork: Additional Excavation and Backfill
Margaret Ann Crigler Park Perkins & Will, PLLC, d/b/a Perkins&Will
Jackson, Mississippi Allen Pratt, Landscape Architect
Construction Documents 802119.000

1. Unit of Measure: Dollars ($) per Cubic Yard (CY)
2. Description: For areas in addition to those required by the contract documents: undercut and removal of existing unsatisfactory fill materials and spoil off site, and material backfill with satisfactory imported fill materials per the project specifications (measured as compacted in place volume). Includes all material, equipment, labor and overhead.

$_____

B. Unit Price No. 2 - Army Worm Integrated Pest Management Pay Item

1. Unit of Measure: Each or Acre
2. Contractor to establish a pay item for monitoring and applying labeled herbicides to control armyworms and related landscape pests in turf, ornamentals, and landscape features, as part of the project's Integrated Pest Management (IPM) program.
3. Section 32 93 00 - Plants for IPM and Armyworm treatment specifications.

$_____